

III SCHEDULE - B					
Name Of Work : Building Exterior Designing Work which includes Supply & fixing of Aluminium Structural Glazing Work ,Panel Cladding using MPAL & Toughened Glass					
Name Of The Contractor :					
GST-No:					
SI No	Description	Quantity	Unit	Contractor Part	
				Rate	Amount
1	2	3	4	7	8
1	ACP Cladding Work:- Providing & Fixing aluminium composite panel (M/s. Eurobond,Aludecor,PIONEER or equivalent) for roofing , Elevation using 49mm (3.5mm)thick sheet as per the approve profile as per the selected shade in image. The rate also including with aluminium back framing of size 2" x I" x 1 .20mm thick & distance as require on site. the rate inclusive of bending the ACP sheet, cutting & making opening in the sheet to make the approved profile I design , The rate inclusive of treating the points with silicon sealant after fixing masking tape , applying double side tap over the section , necessary SS screws, SS bolts and nuts etc., complete. The rate is inclusive of materials , tools and labours and etc.				
2	Scaffolding,leed,lift charges				
	AMOUNT				
	GST 18%				
	Total Amount				
Contractor/ Proprietor					